Bruhath Benglauru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.
Schedule - B

Name of the Work :Construction of RCC drains in 16th B & 16th C cross BHEL Mini colony road in ward no. 13 Shettyhalli sub division

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted **Jnanendra Murthy. MD**	
				In Figures (Rs)	In Words (Rs)
1	Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods Complete Asper the Directon Of Enggineer -in-charge of the work	CUM	291.6	176.30	Rupees One Hundred and Seventy Six and Thirty Only
2	Removing B S Slab Drain And Stacking Asper the Directon Of Enggineer -in-charge of the work	SQM	432	65.00	Rupees Sixty Five Only
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	38.12	4443.00	Rupees Four Thousand Four Hundred and Fourty Three Only
4	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	10.48	5159.00	Rupees Five Thousand One Hundred Fifty Nine Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted **Jnanendra Murthy. MD**	
				In Figures (Rs)	In Words (Rs)
5	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	129.6	5874.00	Rupees Five thousand Eight Hundred and Seventy Four Only
6	Providing and removing centering, shuttering, strutting,. propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached1 pilasters, buttresses, plinth cilis and string courses cost of all materials, labour Asper the Directon Of Enggineer -in-charge of the work	SQM	1152	310.00	Rupees Three Hundred and Ten Only
7	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Asper the Directon Of Enggineer -in-charge of the work	Tonne	7.13	64243.00	Rupees Sexty Four Thousand and Two Hundred and Fourty Three Only
8	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Asper the Directon Of Enggineer -in-charge of the work	SQM	14.04	1680.00	Rupees One Thousand and Six Hundred and Eighty Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division